

#### **SITE INFORMATION**


*SURVEY DA	ATE: A	oril 26, 2	2013	*ADDRESS:	4535	5 312	2 <sup>th</sup> St	reet			
*SURVEYOR: Jim Stone				*COUNTY:							
				*CITY:	Gayv	ille					
LOCATION DESCRI	PTION: FI	om Ver	million, South	Dakota Highwa	y 50 We	st to	Med	klin	g, co	ntinu	ıe West
on Highway 50, 3-1/	4 miles to 3	12 <sup>th</sup> stre	eet, turn left(Sc	uth) then (West	) about	½ n	nile o	n th	e left	t (Sou	uth)
side.											
LEGAL DESCRIPTION	ON: NE 1/	Evol	A+ U 1 9 U 2 9	Eva N 500' of E	350' of '	M 50	)5' of	. NIVA	/ 1/. N	JE 1/.	
20 – 93 – 53 Meckli		, EXC L	01 H-1 & H-2 &	EXC N 300 OI E	330 01	VV JC	) UI	INVV	/4, I	NE /4,	,
20 - 33 - 33   WECKII	iig iwp.										
					Wade A., William H. Sr. & Jane A.						
*QUARTER 1:	NE1/4			OWNER NAME:							
*QUARTER 2:			OWN	31377 454 <sup>th</sup> Ave.							
*TOWNSHIP:	Meckling			OWNER CITY:	Meckling						
*RANGE:	53			WNER STATE:	South Dakota						
*SECTION:	20			OWNER ZIP:	57069						
ACRES:	155.79			QUAD NAME:							
OWNER CODE 1:	Р										
OWNER CODE 2:											
OWNER CODE 3:											
HISTORIC SIGN	IFICANCE										
				DECISTED NA	AME.						
*DOE:				REGISTER NAME: MULTIPLE PROPERTY NAME:							
*DOE DATE:				WIULTIPLE PR	OPERI	T IN	AIVI E	_			
REASON INELIGIB	LE:										
					c	ATE	GOF	RY:			
NOMINATIO		SIGNIFICANCE LEVEL 1: N S L									
	TE LISTED:		_		FICANCE LEVEL 2: N S L				L		
REFERENCE	NUMBER:										
HISTORIC DISTRIC				CRITI	ERIA 1:	Α	В	С	D		
	PERIOD:			CRITI	ERIA 2:	Α	В	С	D		
				CRITI	ERIA 3:	Α	В	С	D		
				CRITI	ERIA 4:	Α	В	С	D		
SIGNIFICANCE NO	ΓES:										



STRUCTURE DETAILS												
SHPO ID:												
*PROPERTY NAME:		<del>-</del>										
OTHER NAME:												
• · · · · · · · · · · · · · · · · · · ·												
CURRENT FUNCTION:	Vacant	FOUNDATION										
CURRENT SUBFUNCTION:	Storage	ROOF MATERIAL	Steel over cedar shingles									
HISTORIC FUNCTION:	Livestock barn	_ ROOF MATERIAL										
	Hay & grain storage	STRUCTURAL SYSTEM										
HISTORIC SUBFUNCTION.	Hay & grain Storage		: Gambrel roof barn									
OCCUPIED:	Vac		Livestock barn									
OCCOPIED.	162	ITPE	2x6 studs, 1x18									
			sheathing and									
	Yes with		½"x6" cedar lap									
ACCESSIBLE:	permission	WALLS:	siding									
STORIES:	2	SIGNIFICANT PERSON:	William Larson									
*DATE OF CONSTRUCTION:		JLTURAL AFFILIATION:	Norwegian									
2711 2 01 0 0 11 0 11 10 11 10 11			- 110: Hogian									
ALTERED/MOVED NOTES:	Original site. Any evide	ence of horse stalls and milk c	ow stanchions has									
<del>-</del>		vith steel roofing. Granary in t										
		ring a horse stall. A lean-to wa										
end much later.	•											
INTERIOR NOTES: The orig	inal barn had two rows	of 4x6 posts and (3) 2x6 lamin	ated posts and a 6x6									
		the posts are laminated with (										
(4) at the north end. These posts are (2) 2x6's with a 2x4 in the center, which created a groove to receive												
the dividers for the horse sta	·	·										
OTHER NOTES: 2x6 stud walls with 8" sheathing and ½"x6" cedar lap siding. Rafters are 2x6's with												
some steel over cedar shingles. All of the dimension lumber and sheathing is rough sawn Black Hills												
pine from Hills, South Dakota. Metal cupola is still in place, which had a horse weathervane. The owner												
· · · · · · · · · · · · · · · · · · ·		about restoring the weatherva	ine.									
	s in good condition.											
		nchions face the gable ends a	nd the doors are on									
the long sides with the alleys	running the width of the	e barn.										
*UTM ZONE:		*RESTRICTED: Y	or N									
*IITM EASTING.												
*UTM NORTHING:												

<sup>\* =</sup> REQUIRED FIELD









PHOTOGRAPHER: Jim Stone ROLL NUMBER: DATE OF PHOTO: April 26, 2013 PHOTO NUMBER: 1
CAMERA DIRECTION: Looking NE, SW corner



PHOTOGRAPHER: Jim Stone ROLL NUMBER:

DATE OF PHOTO: April 26, 2013 PHOTO NUMBER: 2

CAMERA DIRECTION: Looking NW, SE corner





PHOTOGRAPHER: Jim Stone ROLL NUMBER: DATE OF PHOTO: April 26, 2013 PHOTO NUMBER: 3

CAMERA DIRECTION: Looking SW, NE corner



PHOTOGRAPHER: Jim Stone ROLL NUMBER: DATE OF PHOTO: April 26, 2013 PHOTO NUMBER: 4
CAMERA DIRECTION: Looking SE, NW corner





PHOTOGRAPHER: DATE OF PHOTO:

Jim Stone April 26, 2013

**ROLL NUMBER: PHOTO NUMBER:** 

First floor, looking SW, 4x6 posts, 6x6 beam and

CAMERA DIRECTION: 2x8 joists



PHOTOGRAPHER:

Jim Stone DATE OF PHOTO: April 26, 2013

**ROLL NUMBER: PHOTO NUMBER:** 

First floor, looking NW, Granary was in this NW corner, posts are (2) 2x6's with a 2x4 in the center creating a groove for partitions for horse

**CAMERA DIRECTION:** stalls.





PHOTOGRAPHER: DATE OF PHOTO:


Jim Stone April 26, 2013

**PHOTO NUMBER:** 

Hayloft, looking NE, 2x6 bracing 4' O. C. and 2x6

**CAMERA DIRECTION: rafters.** 





© Farm & Home Publishers, Ltd.

27

CLAY CO., SD

### **HISTORY**



This farm located in the NE ¼ of Section 20, Meckling Township, Clay County was homesteaded by John A. Stephenson.

The 1892, 1901 and 1912 Clay County Atlas lists M. N. Richardson and Wm. McClelland as the owners.

The 1924 Clay County Atlas lists M. N. Richardson as the owner.

The 1937 Clay county Atlas lists T. McClelland as the owner and William Larson as the operator.

The 1948 and 1956 Clay county atlas lists William Larson as the owner. Willhelm Larson changed his name to William Larson with no middle name. He was the grandfather to William H. Larson Sr. who owns the farm now.

#### The Following Is Furnished by

William (Bill) Larson Sr., who owns this farm.

In the 1930's, with the terrible drought, hay was is great demand in western South Dakota. William Larson was baling grass hay from the Missouri River bottom and hauling it to western South Dakota. He would drive on to Hills, South Dakota and pick up a load of lumber direct from the lumber mills and haul it back to the Gayville, Meckling and Vermillion area. He had a 1933 Chevrolet truck. In 1938 he decided to build a new barn on his farm. He hauled the lumber back from Hills, South Dakota to build his new barn. The lumber cost \$700.00. His grandson Wm. (Bill) Larson does not remember how many loads it required for this barn. The lumber is rough sawn and oversized. The 2x6's measure 6-1/4" wide and the 2x8's measure 8-1/4" wide. The sheathing boards are just over 3/4" thick and 8" wide.

The builders were Royal Lunde and Robert Brinstall who were partners in a contracting business. William Larson assisted the builders. All of the lumber was sawn by hand just NW of the barn. Royal Lunde and Robert Brinstall also built a barn about 1-1/2 miles West and ½ mile North of this barn. The two barns were known as the "sister barns", because they were almost exactly alike. This barn is 26' wide and the other barn was 28' wide. The other barn had six double horse stalls and was a horse barn. This barn had two or three double horse stalls and stanchions for milk cows.

